

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 17, 1879, under GLO contract No. 319, as follows:

Set basalt stone 18" x 14" x 7" on southwest face of mountain. Drove stake and built a mound of stones around both.

T3S R31E
S18!S17
S19!S20
PLS 1636
1998

In April, 1978, John E. Hollingsworth, PLS 691, recovered the original corner stone. See drawing O-9-C, Umatilla County Surveyor's Office.

Corner evidence recovered:

Found the original corner stone loosely set on the northeast edge of a mound of stones. The corner stone is 19" x 14" x 9" and is plainly marked with three notches on the north edge and three notches on the south edge. A "State Parks" location sign is attached to a piece of iron with wire and is lying alongside the corner stone. This sign was probably placed by Hollingsworth. The original stake is gone.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe 18" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown above. I bury the corner stone, the "State Parks" sign and the iron it is wired to, along the northwest side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S17", attached at ground level, bears N33°E, 69.2 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S20", attached at ground level, bears S71°E, 66.8 feet.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S19", attached at ground level, bears S63°W, 88.1 feet.
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S18", attached at ground level, bears N32°30'W, 157.2 feet.

A steel fence post with a "Witness Post" sign attached bears N62°W, 2.3 feet.

This corner is about 200 feet north-east of State Highway No. 395.

I hereby certify the above corner point was perpetuated as hereon described on June 2, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renewal 6/30/99

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 7-98
Rec'd By KR
No. 98-141-R