


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-25

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner a 8" dia Pine was set from which:



- A 6" dia Pine bears N40°E 22 lk dist.
- A 7" dia Pine bears S6°E 40 lk dist.
- A 14" dia Pine bears S68°W 40 lk dist.
- A 10" dia Pine bears N28°W 20 lk dist.

No record of restoration appears in County Records.

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

The position of this corner was re-established by single proportionate measure along the range line between the East 1/4 of Section 25, T3S R31E, W.M. and the East 1/4 of Section 24, T3S R31E, W.M. At the re-established corner I set:
2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground with mound of stone from which:

- A 10" Red Fir bears N66°W 73.7 ft dist marked: T3S R31E S24 BT.
- A 8" dia Red Fir bears S19°W 28.3 ft dist marked: T3S R31E S25 BT.

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 and 4 signs. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush. Set steel fence post with 54-2 and 4 signs, North of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 18, 1982.


Cap marked:

Witnessed by: Leslie E. Wilson

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15th day of November, 1982

Davis (COUNTY OFFICIAL) *Betty L. Shatto* (DEPUTY)

RECEIVED BY
* GPO-788-276
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-137-B