

USDA-FOREST SERVICE

Index File No. R-25

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 25 Cor. No. NE Cor

T 3S R. 31E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



T3S R32E  
S24 S29  
 S25  
 R31E

DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner was re-established by single proportion measure along range line.

PHOTO IDENTIFICATION DATA

Photo No. 616140 780-7  
 Filed At Umatilla Nat. Forest  
 Object Ident. Trees  
 Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Yellow Jacket Road South to road #5415, then East on road #5415 approx. 3/4 mile to cattleguard and N-S fence, then 250 ft North on West side of fence in timber to corner.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
*Agency*

Signature

*Willie R. Wells*

Title

PLS 1106

Division

Headquarters

Date

October 18, 1982

7100-52-(3-68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground with mound of stone.

Set steel fence post, with 54-2 and 4 signs attached, North of corner.  
Cap marked:

R3S R32E  
S24 | S29  
S25 |  
R31E  
1982  
PLS 1106

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 10" dia Red Fir bears N66°W 73.7 ft dist marked: T3S R31E S24 BT.

A 8" dia Red Fir bears S19°W 28.3 ft dist marked: T3S R31E S25 BT.

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 and 4 signs.  
New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/18/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared ? Yes  No  Filed At: Umatilla County Surveyor Office Date

**REMARKS**

Witnessed by: Leslie E. Wilson