

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

---


History of original corner establishment:

Index: T-21

1/4 Corner to sections 25 & 26, T.3S., R.31E., W.M.  
Original corner was set by George S. Pershin under  
Contract Number 319 in 1879.

His record reads:

Set Basalt stone 18x8x5 on east slope for 1/4  
Section Corner, from which  
A fir 8" ins. diam. bears N 52° 0' E, 54 lks. dist.  
A pine 18" ins. diam. bears S 12° W, 33 lks. dist.



Description of corner evidence found:

Found the original stone firmly in place in a mound of stone. The 1/4 was plainly visible on the west side of the stone. A decayed pine stump was S 12° W, 23.1' from the stone. The stump was cut below the level of the scribing found on other existing bearing objects set by the original project.

Description of monument and accessories I established to perpetuate the

original location of this corner:

The bearings were based on the record bearings of the existing witness stump.

I set a 2 1/2" brass disk on a 30" galvanized Iron Pipe on bedrock 18" below the surface of the ground at the location of the original stone. A mound of stone was erected around the monument and the monument marked as in the diagram above. The original stone was buried along side.

I set the following new witness trees:

A 14" dbh Ponderosa Pine bears S29°16'W, 79.0' scribed 1/4S26BT.

A 9" dbh Ponderosa Pine bears S72°42'W, 46.7' scribed 1/4S26BT.

A 14" dbh Ponderosa Pine bears N52°51'W, 82.0' scribed 1/4S26BT.

A 9" dbh Ponderosa Pine bears N24°01'E, 27.5' scribed 1/4S25BT.

A Brass washer stamped ORLS 852 and WALS 13922 is nailed between the letters B and T on the new trees. All the BT's have BT signs attached. Painted 2, 1" red bands around all the trees and painted the scribe blazes red. Placed a 6' steel post by the mound with a Umatilla County Land Survey Monument sign on it.

This work was done October 17, 1995 and witnessed by Stephen K Haddock.

Office of Survey Dept. County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed  
in this office for record on the 23rd day of October, 1995.

( COUNTY OFFICIAL )

( DEPUTY )

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 10-95  
Rec'd By KK  
No. 95-184-R

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1968  
DAVID L. HADDOCK  
852