


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-25

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner position a Fir post was set on nearly level ground for 1/4 corner from which:



- A 9" dia Pine bears East 8 lk dist.
- A 10" dia Fir bears West 28 lk dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" I. pipe projecting 3" out of ground from which:

- A 8" Spruce bears S37 1/2° W 35.1 ft dist tagged N37 1/2° E 53 lk dist (recent BT).
- A 17" dia White Fir bears West 18.7 ft dist tagged East 28 lk dist (old BT healed blaze).
- A 10" dia Lodge Pole Pine Snag bears East 5.2 ft dist tagged West 5.2 ft dist (old BT visible scribing).


Description of monument and accessories established to perpetuate the original location of this corner:

- Set steel fence post with 54-2 and 4 signs 5 ft North of corner.
- Blaze faces and 6" band around bearing trees were painted red. Tagged trees with 54-3 and 4 signs where needed.
- Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on September 29, 1982.

Standard BLM cap. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County Surveyor..... County of..... Umatilla  
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the 15<sup>th</sup> day of December, 1982  
 David A. Humberby (COUNTY OFFICIAL) Betty L. Shatto (DEPUTY)

RECEIVED BY  
 Umatilla County Surveyor  
 Date \_\_\_\_\_  
 Rec'd By \_\_\_\_\_  
 No. 82-137-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of sec. 25 only, on the E. bdy. of the Tp., determined at record bearing and distance from the remains of the original bearing trees:

A Pine Snag, 11 ins. diam., bears East, 8 lks. dist., with scribe marks  
1/4 S BT visible on open blaze.

A Fir, 18 ins. diam., bears West, 28 lks. dist. with healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap marked:

T3S  
R31E R32E  
1/4 S25  
1978

from which a new bearing tree

A Spruce, 8 ins. diam., bears S. 37 1/2° W., 53 lks. dist., mkd. 1/4 S25 BT.

RECEIVED BY

Umatilla County Surveyor

Date \_\_\_\_\_

Rec'd by \_\_\_\_\_

No. 82-137-B