


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-15

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a 17" x 11" x 7" basalt stone was set on level for 1/4 corner from which:



A 6" dia Pine bears N60°W 105 lk dist.  
A 18" dia Pine bears S12°W 108 lk dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe in mound of stone from which:

A 29" dia Ponderosa Pine bears N57°W 74.1 ft dist tagged S57°E 74.1 ft dist (old BT, visible scribing).  
A 13" dia Ponderosa Pine bears S16°W 174.0 ft dist tagged N15°E 262 1/2 lk dist - recent blaze.


Description of monument and accessories established to perpetuate the original location of this corner:

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 4 signs where needed. Set steel fence post with 54-4 sign attached, West of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTS.

Corner ~~monumented~~ on October 6, 1982.  
*maintained*

Standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of.....County Surveyor..... County of.....Umatilla.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the 15<sup>th</sup> day of December, 1982

*Daniel F. Kruse* bears by *Betty L. Shatto*  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
★ GPO-799-276  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd - y \_\_\_\_\_  
No. 82-138-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 27 and 34, monumented with the original unmarked basalt stone, 24 x 11 x 7 ins. (record, 17 x 11 x 7 ins.), firmly set 15 ins. in the ground, and in a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A pine, 22 ins. diam., bears N. 60° W., 115 lks. dist., with scribe marks  
BT visible on open blaze. (Record, 105 lks.)

A sawed and decayed pine stump, size indeterminate, bears S. 12° W., 114 lks.  
dist., no marks visible. (Record, 108 lks.)

At the corner point

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R31E  
1/4  $\frac{S27}{S34}$   
1978

from which a new bearing tree

A ponderosa pine, 12 ins. diam., bears S. 15° W., 262 1/2 lks, dist., mkd. 1/4 S34 BT.

Deposit corner stone alongside iron post.

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd by \_\_\_\_\_  
No. 82-138-B