

Index  
File No. V-15

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or Survey No. Sec 34 Cor. No. N 1/4 <sup>12</sup>

T 3S R. 31E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

**CORNER DIAGRAM**

T3S R31E  
1/4 S27  
S34



**DESCRIBE CORNER MONUMENT FOUND**

3" brass cap on 2 1/2" l. pipe in mound of stone.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

A 29" dia P. Pine brs N57°W 74.1 ft dist tagg S57°E74.1 ft dist (old BT visible scribe).  
A 13" dia P. Pine brs S16°W 174.0 ft dist tagg N15°E 262 1/2 lk dist-recent blaze.

**PHOTO IDENTIFICATION DATA**

Photo No. 616140 380-4

Filed At. Umatilla Nat. Forest

Object Ident. Trees

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER.**

Road #5420 to road #5412-100, then West approx. 2.1 miles on road #5412-100, then 40 ft North to corner in Swiss Meadows, just North of timber line and fence.

Signature

*Willie R. Wells*

Title

PLS 1106

Division

Headquarters

Date

October 6, 1982

7100-52 (3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set steel fence post with 54-4 sign attached, West of corner.  
Standard BLM.

Cap marked:

T3S R31E  
1/4  $\frac{S27}{S34}$   
1978

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 and 4 signs, where needed.

Work Done By W.R. Wells Title Surveyor Date 10/6/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date \_\_\_\_\_

**REMARKS**

Witnessed by: Leslie E. Wilson

Index File No.  
V-15

T.

3S

R.

31E

M.

W.M.

Tract or Surv. No.

Sec 34

Cor.

N 1/4

12

13

Index File No. V-15

CORNER RECORD (SEARCH)

Tract or Survey No. 5-39 Cor. No. V-15


T 3S R. 31E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Material: Stone mound. Size: Mound 24-inch diameter.  
 One foot above ground; good condition.  
 No markings visible. Stone is approximately the same as G.L.O. description is set in the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

An 18-inch p.pine bears N60°W, approximately 70 feet. It has old "Oregon State Board of Forestry" location poster. Some scribing visible (B.T.).  
 A 20-inch, partially rotted pine stump bears S12°W, approximately 70 feet. No scribing visible, but it fits the proper location.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By. \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

corner is about 50 feet north of main road from Carney Butte to Bear Wallow G.S.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
*Agency*

See Carney Butte 7.5 minute quadrant map. A fence corners about 20 feet SE of the B.T. stump. Fences run approximately south and west.

Signature	Title	Division	Headquarters	Date	7100-52
T. Hollamon	Engineering Technician		S. O.	November 1, 1974	REV. 65 5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

I set a loose post in the stone mound and tied red and white striped ribbon on it.

I placed blank B.T. tags on both the B.T. and the B.T. stump.

10

Work Done By \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_ State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes No Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

REMARKS

12

Index File No. T. R. M. Tract or Surv. No. Cor. \_\_\_\_\_

13