


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-21

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a 20" x 12" x 4" basalt stone was set in mound of stone in small open glade sloping North from which:



- A 14" dia Pine bears N63°E 250 lk dist.
- A 30" dia Pine bears S62°E 95 lk dist.
- A 12" dia Fir bears S10°W 127 lk dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

**Description of corner evidence found:**

3" brass cap on 2 1/2" I. pipe protruding 12" out of ground in mound of stone in clearing on slight North slope from which:

- A pine Stump bears N60°E 163.5 ft dist - (old BT) deteriorated.
- A 28" dia Pine Stump bears S10°W 83.5 ft dist - (old BT) open blaze with visible blaze.
- A 40" dia P. Pine bears S58 1/2°E 62.0 ft dist tagged N62°W 95 lk dist-(old BT) open blaze.
- A 15" dia P. Pine bears N43°E 69.2 ft dist tagged S43°W 104 lk dist -(recent blaze.)
- A 19" dia P. Pine bears N43°W 69.5 ft dist tagged S41 1/2°E 105 lk dist -(recent blaze.)
- A 13" dia Red Fir bears S19 1/2°W 63.8 ft dist tagged N19°E 97 lk dist - (dead BT) recent blaze).

**Description of monument and accessories established to perpetuate the original location of this corner:**


Set steel fence posts with 54-2 signs on both and 54-4 sign on one South and East of the corner.

A 10" dia Red Fir bears S82°W 87.0 ft dist marked: T3S R31E S35 BT. (new BT)

Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54 - 3 and 4 signs where needed. Each new BT has a lower blaze, scribed BT, with brass washer nailed flush. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 4, 1982 .

Cap is standard BLM. Cap marked:



**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

*Darvisch*  
(COUNTY OFFICIAL)

*Billy J. Shatto*  
(DEPUTY)

**RECEIVED BY**

**Umatilla County Surveyor**

Date \_\_\_\_\_

Rec'd By \_\_\_\_\_

No. 82-137-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 25, 26, 35, and 36, determined at record bearing and distance from the remains of the original bearing trees:

A sawed and decayed Pine Stump, size indeterminate, bears N. 63° E., 250 lks. dist., no marks visible.

A Pine, 40 ins. diam., bears S. 62° E., 95 lks. dist., with scribe marks R31E visible on open blaze.

A sawed Pine Stump, 28 ins. diam., bears S. 10° W., 127 lks. dist., with scribe marks S35 visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 18 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S	R31E
S26	S25
S35	S36
1978	

from which new bearing trees

A Ponderosa Pine, 15 ins. diam., bears N. 43° E., 104 lks. dist., mkd. T3S R31E S25 BT.

A Fir, 13 ins. diam., bears S. 19° W., 97 lks. dist., mkd. T3S R31E S35 BT.

A Ponderosa Pine, 18 ins. diam., bears N. 41½° W., 105 lks. dist., mkd. T3S R31E S26 BT.

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-137-B