


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-25

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner position a 20" x 16" x 7" stone was set on N.W. slope, from which:



- A 8" dia Pine bears N36°E 28 lk dist.
- A 6" dia Pine bears S70°E 33 lk dist.
- A 7" dia Pine bears S74°W 47 lk dist.
- A 10" dia Tamarack bears N28°W 48 lk dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" I. pipe protruding 4" out of ground with mound of stone from which:

- A 10" dia L.P. Pine bears S17°W 12.3 ft dist tagged N14 1/2°E 19 1/2 lk dist - (recent blaze, dead).
- A 10" dia Grand Fir bears N83 1/2°W 49.3 ft dist tagged S84°E 74 1/2 lk dist - (recent blaze)
- A 16" dia Tamarack bears N 25 1/2° W 32.6 ft dist. (old BT, visible scribing).

Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence posts with 54-2 signs on both and 54-4 sign on one, North and West of corner.

A 18" dia Grand Fir bears S63°W 51.2 ft dist marked: T3S R31E S36 BT.


Blaze faces and 6" band around bearing trees were painted red. Tagged trees eith 54- 3 & 4 signs where needed. Each new BT has lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to the center of BTs.

Corner was maintained on September 30, 1982.

Cap is standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County Surveyor..... County of..... Umatilla
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 15th day of November, 1982
 .. David H. Krumbein by Betty L. Shatto
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY 798-276
 Umatilla County Surveyor
 Date _____
 Rec'd by _____
 No. 82-137-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 25 and 36 only, on the E. bdy. of the Tp., monumented with the original basalt stone, 20 x 16 x 7 ins., firmly set 8 ins. in the ground, mkd. with 5 notches on N. edge, from which the remains of the original bearing trees:

A Larch Snag, 14 ins. diam., bears N. 28° W., 48 lks, dist., with scribe marks 3S R31E S25 visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass marked:

T3S		T3S
S25		R32E
S36		
R31E		S32
		1978

from which new bearing trees

A White Fir, 12 ins. diam., bears N. 84° W., 74½ lks. dist., mkd.
T3S R31E S25 BT.

A Lodgepole Pine, 11 ins. diam., bears S. 14½° W., 19½ lks. dist., mkd.
T3S R31E S36 BT.

Deposit corner stone alongside iron post.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-137-B