


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

W-15

History of original corner establishment:

None.

No record of corner establishment found in County Records.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 26" in ground with mound of stone from which:

A 8" dia Lodge Pole Pine bears N71°W 25.6 ft dist marked: CN 1/16 S34 BT.

A 16" dia Tamarack bears S4°E 32.1 ft dist marked: CN 1/16 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 9 signs.

New BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.


Set steel fence post with 54-9 sign on one and 54-2 signs on both, South and East of the corner.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 20, 1982.

Cap marked:

Witnessed by: D.L. Kaufman PLS
R. D. English PC
L. D. Henshaw ϕ (rodman)
L. E. Wilson ϕ



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the... 12... day of... December... 1982

... David H. ... by Betty ... (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd by _____

No. 82-138-B