


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-21

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878.



This corner was re-established and re-monumented by PLS 1051 in 1977, by traverse Survey. No original evidence was found by PLS 1051.

Description of corner evidence found:

2 1/2" brass cap on 2 1/2" I. pipe protruding 10" from ground from which:

A 10" dia W Fir bears N38°E 8.0 ft dist tagged S38°W 8 ft dist (recently blazed).

A 12" dia W Fir bears N 38½°W 37.8 ft dist tagged S38°E 38 ft dist (recently blazed).

A steel fence post with 54-4 sign attached, 4 1/2 ft East.

Description of monument and accessories established to perpetuate the original location of this corner:

Set Steel fence post with 54-2 and 4 signs attached, 4 1/2 ft North of corner.


Blaze faces and 6" band around bearing trees are painted red.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 4, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15th day of December....., 1982

David H. P. ... (COUNTY OFFICIAL) by *Betty L. Shatt* (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-137-B