


History of original corner establishment.

Corner established in November, 1878 under GLO Contract. Surveyor General's notes state:

- "Set pine post on nearly level ground for corner to section 35, 36, 1 and 2, from which:
- A pine 10" in dia. bears N54°E, 42 lks. dist.
- A pine 9" in dia. bears S74°E, 23 lks. dist.
- A pine 11" in dia. bears S43°W, 26 lks. dist.
- A pine 10" in dia. bears N30°W, 28 lks. dist.



Description of corner evidence found:

None found.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2½"x30" galvanized pipe with brass cap marked:  
 Set pipe 24" in the ground, with mound of stone around.  
 From which: A fir 9" in dia. bears 7.9' scribed T3S R31E S36 BT.  
 A fir 12" in dia. N38°W, 37.9' scribed T3S R31E S35 BT. Placed  
 54-3s and 54-4s on BT's, brass washer on BT blaze, stamped PLS 1051.  
 Placed 54-2 and 54-4 on fence post 4' east of corner.  
 Painted 6" red bands and both blazes red.

T3S R31E  
 SC  
 S35 | S36  
 T4S R32E  
 OR PLS 1051  
 1977

I hereby certify the above corner monument was re-established as herein described.

Witnesses: D.L. Landers  
 S. Nelson  
 November 8, 1977  
 See Record Plat for  
 S6, T4S, R32E, W.M. as  
 filed with the Umatilla  
 County Surveyor.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Barry B. Barbour*

OREGON  
 OCT. 17, 1975  
 BARRY B. BARBOUR  
 1051

Office of..... County of Umatilla  
 State of Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)