

USDA-FOREST SERVICE

Index File No. Z-25

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____ Sec. _____


T 3S R. 31E

R.D. Ukiah County Umatilla

Merid. W.M.

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 20"x14"x6" basalt stone completely covered by dirt. Dimly notched with 6 notches on edges.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A Tamarac 21" in dia. bears N20°E, 12.5 feet with some scribing visible. No trace of other BTs.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 250' northwest of Cold Spring and near corner of Forest Boundary fence.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____

Signature

Berry B Barber

Title

P.L.S.

Division

Headquarters

Date

11/9/77

7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

GPO 902-873

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At corner position set 2½"x30" galvanized pipe with brass cap,
marked:
Set pipe 24" in the ground and placed corner stone at base of pipe.

T3S T4S
R31E R32E
S36
OR PLS 1051
1977

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which: A Fir 9" in dia. bears N52°W, 43.6 feet, scribed T3S, R31E, S36 BT.
Placed 54-3s and 54-4 on trees, brass washer on BT blaze, stamped PLS 1051.
Painted 6" red band and both blazes red.
Placed 54-2s and 54-4s on fence posts, 5' north and west.

Work Done By B.B. Barbour Title P.L.S. Date 11/9/77 State Registration No. or Agency OR PLS 1051

Certified Cor. Record Prepared ? Yes No Filed At: Date

REMARKS

Index File No. T. R. M. Tract or Surv. No. Cor.