


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 13
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 22, 1882, under GLO contract No. 430, as follows:

Set basalt stone, 18" x 14" x 12", in a mound of stone on west slope, marked 1/4 on west face. Raised a mound of stones in lieu of pits.



Corner evidence recovered:

Found the original corner stone loosely set in a mound of stones in an east-west barbed-wire fence. Corner stone is 18" x 12" x 10" and is plainly marked "1/4".

Monument and accessories established to perpetuate the original position of this corner:

At the position occupied by the original corner stone, I set a 1" x 30" iron pipe 18" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N41°E, 100.0 feet.
A 5/8" x 36" iron rod set 30" into the ground in a small mound of stones, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S25°E, 134.5 feet.

A 27" Ponderosa Pine, scribed "1/4 S4 BT" on double blazes with a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", bears S31°15'W, 240.0 feet. This tree has a "Bearing Object" sign nailed above the blazes.

A 5/8" x 36" iron rod set 30" into the ground in a small mound of stones, with a 3/4" brass washer, marked "PLS 1636 S4", attached at ground level, bears N28°30'W, 81.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on August 27, 1999. Magnetic declination: 18°E

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1999.

RECEIVED BY

Umatilla County Surveyor

Date 9-99

Rec'd By RR

No. 99-1248-R