

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 22, 1882, under GLO contract No. 430, as follows:

Set basalt stone, 14" x 12" x 5", marked "1/4" on west face, from which:

- A 15" pine bears S60°E, 41 links (27.06 feet).
- A 10" pine bears S24°W, 46 links (30.36 feet).



Corner evidence recovered:

Found the original corner stone solidly set. The corner stone is 13" x 13" x 5" and is plainly marked "1/4" on the west face, from which:

A sawn 23" Ponderosa Pine stump with scribes, "BT", visible, bears S24°W, 28.7 feet (30.4 feet slope distance).

The original bearing tree to the south east is an uprooted, sawn Ponderosa Pine stump. I am not able to tell where this tree stood.

Monument and accessories established to perpetuate the original position of this corner:

At the position occupied by the original corner stone, I set a 1" x 30" iron pipe 24" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 15" Douglas-fir, scribed "1/4 S2 BT", bears N00°30"E, 33.4 feet.
- A 16" Douglas-fir, scribed "1/4 S2 BT", bears S7°E, 34.6 feet.
- A 11" Ponderosa Pine scribed "1/4 S3 BT", bears S22°W, 51.6 feet.
- A 13" Ponderosa Pine scribed "1/4 S3 BT", bears N49°W, 63.0 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B". The new bearing trees and the original bearing tree stump to the south west have "Bearing Object" signs nailed above the blazes. The bearing tree to the north west has a "Witness Post" sign nailed to the back side of the tree.

I hereby certify the above corner point was perpetuated as hereon described on August 27, 1999. Magnetic declination: 18°E



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1999.

RECEIVED BY
Umatilla County Surveyor
Date 9-99
Rec'd By. [Signature]
No. 99-149-R