


History of original corner establishment:

This corner was originally established by George S. Pershin under G.L.O. contract no. 430 dated March 23, 1882. He set a basalt stone 18"x10"x5", 12" in the ground. The stone was marked 1/2 on the north side.

From the corner:
A P. Pine, 40" dia., N14°E, 155 lks.

No other BT was available; he raised a stone mound alongside the corner.



Description of corner evidence found:

Found no acceptable evidence of the original corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

At proportionate distance set a 2 1/2"x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

T3S R32E

1/2 S1

S12

PLS 1832

1984

Built a stone mound around the monument.

Marked BTs:

A P. Pine, 14" dia., N17 1/2°E, 38.9 ft. marked: 1/2 S1 BT

A P. Pine, 11" dia., S16 3/4°E, 32.6 ft. marked: 1/2 S12 BT

BTs have blaze and a 6" stripe painted red, a BT tag, an "Attention" sign and an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 18 1/2°E.

August 30, 1984.

REGISTERED PROFESSIONAL LAND SURVEYOR

Fayette S. Munro

OREGON JULY 13, 1979 FAYETTE S. MUNRO 1832

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 10 day of October, 1984
David H. Krumboltz by [Signature]
(COUNTY OFFICIAL) (DEPUTY)

E-23