


History of original corner establishment:

Corner originally established by George S. Pershin in May, 1882, under contract number 430, as follows:

Set a basalt stone, 20" x 10" x 7", on a S.W. slope in a mound of stones, marked 1/4 on west face. No trees near, raise a mound of stones alongside in lieu of pits.



Description of corner evidence found:

Original corner stone, 21" x 11" x 10", is solidly set in a mound of stones. The stone is marked "1/4" on the west face.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1636

*Renewal date 6/30/95*

Description of monument and accessories | established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe 24" into the ground, with a 2 1/2" brass cap attached which is marked as shown in the diagram above. I bury the original stone up-side-down along the south side of the pipe and build up the original stone mound. From which:

A 5/8" x 36" iron rod set 35" into the ground with a 1 1/2" aluminum cap attached bears N23° 30'E, 17.3 feet. This reference monument is in a fence corner with fences projecting north and west. Cap is marked:



A 5/8" x 36" iron rod set 35" into the ground with a 1 1/2" aluminum cap attached bears S68° 30'E, 57.1 feet. Cap is marked:



A 5/8" x 24" iron rod set 21" into the ground with a 1 1/2" aluminum cap attached bears S37° W, 36.6 feet. Cap is marked:



A 5/8" x 24" iron rod set 23" into the ground with a 1 1/2" aluminum cap attached bears N69° 30'W, 41.9 feet. This reference monument is 1.3 feet east of a metal fence post in an east-west fence. Cap is marked:



MAG. DECL: 20° E.

Office of COUNTY SURVEYOR County of UMATILLA  
 State of OREGON, I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 \_\_\_\_\_ by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

**RECEIVED BY**

Umatilla County Surveyor  
 Date 6-95  
 Rec'd By KK  
 No. 95-90-R