


History of original corner establishment:

Corner originally established by George S. Pershing in May, 1882, under contract number 430, as follows:

Set a basalt stone, 14" x 10" x 4", on S.W. slope marked 1/4 on west face, from which:

- A 36" Pine bears S20°E, 77 links. (50.82 feet)
- A 26" Pine bears west, 80 links. (52.80 feet)



Description of corner evidence found:

Original corner stone, 16" x 11" x 4", is solidly set in a mound of stones. The stone is marked "1/4" on the west face, from which:

A sawn and decayed 29" Ponderosa Pine stump with scribe marks, "BT", visible, bears S14°E, 51.8 feet.

A 29" Ponderosa Pine with healed blaze bears N85°W, 52.8 feet.

Description of monument and accessories | established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe 25" into the ground, with a 2 1/2" brass cap attached which is marked as shown in the diagram above. I bury the original corner stone up-side-down along the west side of the pipe and build a mound of stones around the monument. The corner is 3 feet west of a north-south fence. From which:

- A 16" Ponderosa Pine, scribed "1/4 S16 BT", bears S65°W, 23.7 feet.
- A 17" Ponderosa Pine, scribed "1/4 S15 BT", bears S54°E, 34.5 feet.
- A 19" Ponderosa Pine, scribed "1/4 S15 BT", bears N81° 30'E, 34.1 feet.

The three new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the lower blaze. All bearing trees and the bearing tree stump have a reference point sign nailed above the blaze.

Magnetic declination: 20°E.

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON JULY 14 1978 DENNIS L. GAYLORD 1636

Renewal Date 6/30/95

Office of... COUNTY SURVEYOR ... County of... UMATILLA ...
State of... OREGON ... I hereby certify that the within instrument was filed in this office for record on the... day of... , 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 6-95
Rec'd By KK
No. 95-91-R