


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. L-17

History of original corner establishment:

The original corner was established by George Pershin under G.L.O. contract 430, dated March 23, 1882. His record reads:

Set a basalt Stone 20x12x4 in on rocky point in mound of Stone for 1/4 Sec. Cor. marked 1/4 on W. face no trees raised a mound of stone alongside



Description of corner evidence found:

Found small stone mound with 20x12x4 stone with 1/4 chiseled in face. Mound was on old north south fence line just south of jog in newer fence.

Description of monument and accessories established to perpetuate the original location of this corner:

At the recovered position of the original stone, I set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap stamped as shown in the diagram above. Set pipe 18" into the ground. Buried original stone alongside.

Placed a 3' diameter mound of stone around the monument and set a steel fence post 5' north of the monument with Forest Service Land Survey Monument sign attached. Scribed 1/4 S15 BT on a 15" Ponderosa Pine which bears N85°30'W, 15.0'. Scribed 1/4 S14 BT on a 10" Ponderosa Pine which bears S1°00'E, 48.7'. The bearings are magnetic with a declination of 20° East. Each scribe is in a 24" blaze. Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each tree. Painted a 6" red band around the new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was perpetuated as hereon described on October 28, 1987.

Witness: Wilma Nell Haddock, Survey Aide.

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Haddock

OREGON JULY 12, 1968 DAVID L. HADDOCK 352

Office of... Surveyor... County of... Umatilla... State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the 23 day of November, 1987. David L. Haddock (COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Survey Date 12-87 Rec'd By No. 87-68-B

☆ GPO-798-276