

USDA-FOREST SERVICE

Index  
File No. N-7  
T 3S R. 32E  
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 20 Cor. No. N 1/4  
R.D. Ukiah County Umatilla  
N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R32E  
1/4 17/20



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" I. pipe 15" out of ground with mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 24" dia P. Pine bears N82°W 139.0 ft dist tagged S9°E 211 lk dist (old BT, healed blaze).

A 26" dia Tamarack bears S39°W 58.6 ft dist tagged N38°E 90 lk dist (old BT, visible scribe).

PHOTO IDENTIFICATION DATA

Photo No. 616140 780-8  
Filed At. Umatilla Nat. Forest  
Object Ident. Trees  
Ident. By \_\_\_\_\_  
*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Yellow Jacket Road to road #5415, East to road #050, North approx. 1 1/2 miles to road going West across open ridge towards fence (N-S) then North along road to end of road then 300 ft North to corner on East side of drainage in clearing on Westerly face of slope.

Signature

*William R. Well*

Title

PLS 1106

Division

Headquarters

Date

October 4, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post with 54-2 and 4 signs West of corner.  
Cap is standard BLM.

Cap marked:

T3S R32E  
1/4 S17  
S20  
1977

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Blaze faces and band around bearing trees are painted red. Tagged trees with 54-3 and 4 signs where needed.

Work Done By W.R. Wells Title Surveyor Date 10/4/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: Leslie E. Wilson

Index File No. N-7 T. 3S R. 32E M. W.M. Tract or Surv. No. Sec 20 Cor. N 1/4