


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-9

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 1882. The original notes state that at the corner a 14" x 8" x 5" basalt stone was set 10" in ground marked with 3 notches on S and 4 notches on E edges from which:



- A 10" dia Fir bears N17°E 33 lk dist.
- A 14" dia Tamarack bears S62°E 48 lk dist.

No restoration appears in County Records.

Description of corner evidence found:

- A 32" dia Fir Stump bears N15°E 21.78 ft dist - (old BT healed blaze)
- A 18" dia Tamarack Stump bears S60°E 31.68 ft dist - (old BT visible scribing).

Found 17" x 11" x 4" basalt stone lying on surface of ground in vicinity of corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground with mound of earth from which:

- A 11" dia White Fir bears S83°E 45.8 ft dist marked: T3S R32E S21 BT.
- A 8" dia Red Fir bears N24°E 46.3 ft dist marked: T3S R32E S16 BT.
- A 12" dia White Fir bears N65°W 62.3 ft dist marked: T3S R32E S17 BT.
- A 9" dia Red Fir bears S46 1/2°W 11.2 ft dist marked: T3S R32E S20 BT.

A steel fence post with 54- 2 and 4 signs West of corner.


Blaze faces and 6" band around bearing trees painted red. Trees tagged with 54-3 and 4 signs. Each new BT has lower blaze, scribed BT with brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on September 27, 1982.

Cap marked:

Witnessed by: D. L. Kaufman PLS



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of.....County Surveyor..... County of.....Umatilla

State of.....Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

*Daniel H. Krumbein* by *Betty J. Shatto*

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd by \_\_\_\_\_  
No. 82-137-B