

USDA-FOREST SERVICE

Index File No. R-13

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or Survey No. Sec 27 Cor. No. NW Cor

T 3S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

**CORNER DIAGRAM**

T3S R32E  
S21 | S22  
S28 | S27



**DESCRIBE CORNER MONUMENT FOUND**

3" brass cap on 2 1/2"x 28" l. pipe 26" in ground.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

A 16" dia T. bears S55°W 11.0 ft dist tagg N55°E 18lk dist (old BT) Healed blaze.  
A 8" dia R Fir brs N34°W 18.0 ft dist tagg S35°E 29 1/2 lk dist-recent blaze.  
A 9" dia R Fir brs N56°E 20.8 ft dist tagg S56°W 32lk dist-recent blaze.  
A 9" dia R Fir brs S62°E 27.0 ft dist tagg N60°W 42lk dist - recent blaze.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Road #54 to road #5412, West to road #5415, North to road #020, North on road #020 approximately 1 mile then approximately 1,000 ft Northeast to top of ridge and location sign at West end of opening and crown breaking to West and North. Then 150 ft North down steep face to corner.

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

Signature

*William R. Wells*

Title

PLS 1106

Division

Headquarters

Date

September 23, 1982

7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post with 54-4 sign on section line near corner.  
Cap is standard BLM

Cap marked:

T3S R32E  
S21| S22  
S28| S27  
1977

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted 6" band around bearing trees and blaze faces red. Tagged trees with 54-3 and 4 signs as needed.

Work Done By W. R. Wells Title Surveyor Date 9/23/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared ? Yes  No  Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: D.L. Kaufman PLS

Index File No.  
R-13

T. 3S R. 32E

M. W.M.

Tract or Surv. No. Sec 27

Cor. NW cor