


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-17

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner position a basalt stone 16" x 8" x 5" was set. 11" in ground on level marked by 2 notches on S and E edges; from which:



- A Pine 13" dia. bears N88°E 61 lks dists. marked T3S R32E S23 BT.
- A Pine 8" dia. bears S38°E 47 lks dist. marked T3S R32E S26 BT.
- A Pine 36" dia. bears S38°W 145 lks Dist. marked T3S R32E S27 BT.
- A Fir 9" dia. bears N66°W 76 lks dist. marked T3S R32E S22 BT.

Remonumentation was done in 1977 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" I. pipe in mound of stone, from which:

- A 18" R. Fir bears N65°W 51.1 ft. tagged S 64° E 76 lk dist. with chopped open blaze (old BT).
- A 14" P. Pine bears S24°W 56.2 ft. tagged N24°E 85 1/2 lk dist. with recent blaze.
- A 26" P. Pine bears S50°E 31.2 ft. tagged N38°W 47 lk dist. with healed blaze (old BT).
- A 31" P. Pine bears N86 1/2° E 41.7 ft. tagged S 88°W 61 lk dist. with healed blaze (old BT).


Description of monument and accessories established to perpetuate the original location of this corner:

- Set steel fence post with 54-4 sign attached on section line near corner.
- Painted blaze faces and a 6" band around bearing trees red. Tagged trees with 54-3 & 4 signs where needed.
- Used steel tape and magnetic compass 19 3/4° East declination.
- Measured to center of BTs.

This corner was maintained on September 22, 1982.

The Cap is a standard 3" BLM cap marked:

Witnessed by: D.L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County Surveyor..... County of..... Umatilla  
 Oregon.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the 15<sup>th</sup> day of November, 1982  
 David L. Kaufman by Betty L. Slatts  
 (COUNTY OFFICIAL) (DEPUTY)

REC'D BY  
 Umatilla County Surveyor  
 Date \_\_\_\_\_  
 Rec'd By \_\_\_\_\_  
 No. 82-136-B

History of 1977 BLM remonumentation.

The cor. of secs. 22, 23, 26, and 27, monumented with the original basalt stone, 16 x 8 x 5 ins., firmly set 10 ins. in the ground, with 2 notches on S. and E. edges, from which the remains of the original bearing trees:

A Pine, 34 ins. diam., bears N. 88° E., 64 lks. dist., with healed blaze. (Record, 61 lks.)

A Pine, 28 ins. diam., bears S. 48° E., 47 lks. dist., with healed blaze. (Record, S. 38° E.)

A Pine, 17 ins. diam., bears N. 64° W., 76 lks. dist., with scribe mark R visible on partially opened blaze. (Record, Fir, N. 66° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 20 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S	R32E
S22	S23
S27	S26
1977	

from which a new bearing tree

A Lodgepole Pine, 14 ins. diam., bears S. 24° W., 85½ lks. dist., mkd. T3S R32E S27 BT.

Deposit corner stone alongside iron post.

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-136-B