

USDA-FOREST SERVICE

Index

File No. R-19

T 3S R. 32E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah

County Umatilla

N.F. Umatilla

State Oregon

Tract or

Survey No. Sec 26

Cor.

No. N 1/4

CORNER DIAGRAM

T3S R32E

1/4 S23
S26



DESCRIBE CORNER MONUMENT FOUND

Found 16" x 14" x 5" basalt stone set 10" in ground with small mound of stone. Marked 1/4 on North face.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None set.

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-287

Filed At. Umatilla Nat. Forest

Object Ident. Trees

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek Road #54 to road 54-100 then West to road 015 then South 800 ft. to intersection with Skid Road to West, then 1,300 ft. West, then S W 200 ft. from end of spur road to corner.

Signature

William R. Webb

Title

PLS 1106

Division

Headquarters

Date

September 23, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground, with mound of stones.
 Buried original stone alongside (upside down). Cap marked:

T3S R32E
 1/4 S23
 S26
 1982
 PLS 1106

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS, OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 9" R. Fir bears S52°E 19.8 ft. marked 1/4 S26 BT.
 A 11 1/2" Tamarack bears N81°E 26.5 ft. marked 1/4 S23 BT.
 Painted blaze faces and 6" band around bearing trees red. Tagged trees w/54-3 & 4 signs as needed. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.
 Set steel fence posts, with 54-4 sign on section line near corner.

10

Work Done By W.R. Wells Title Surveyor Date 9/23/82 State Registration No. PLS 1106
 or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

11

REMARKS

Witnessed by: D.L. Kaufman PLS

Index File No.
R-19

T. 3S R. 32E

M. W.M.

Tract or Surv. No. S 26

Cor. N 1/4

12

13