


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-21

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a 15"x 8" x 7" basalt stone was set in mound of stones on slight North slope, from which:



- A 18" dia. Pine bears N64°E 134 lks dist. marked T3S R32E S24 BT.
- A 22" dia. Pine bears S38°E 61 lks dist. marked T3S R32E S25 BT.
- A 28" dia. Pine bears N42°W 192 lks dist. marked T3S R32E S23 BT.

Remonumentation done in 1977 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

Found a 3" brass cap on 2 1/2" I. pipe projecting 12" out of mound of stone, from which:

- A 29" P. Pine bears N80°E 89.5 ft. dist. tagged S81°W 186 lks dist. (old BT) healed blaze.
- A 35" P. Pine bears N64°W 129.4 ft. dist. S64°E 195 lks dist. (old BT) open blaze.
- A 30" P. Stump bears S54°E 42.0 ft. dist. (old BT) visible scribing in wood near stump.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set steel fence post, with 54-4 sign attached, on section line near corner.


- A 27" Red Fir bears S13°W 255.5 ft. dist. marked T3S R32E S26 BT.
- A 9" P. Pine bears S48°E 115.0 ft. dist. marked T3S R32E S25 BT.
- New BTs have a lower blaze scribed BT with brass washer stamped PLS 1106 nailed flush.

Painted the blaze faces and 6" bands around the bearing trees red. Tagged trees with 54-3 & 4 signs where needed. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush. Used steel tape and magnetic compass 19 3/4° East declination. Measured to the center of the BTs.

This corner was maintained on September 23, 1982.

The cap is a standard BLM cap marked:

Witnessed by: D.L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County Surveyor..... County of..... Umatilla  
 State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
 for record on the 15<sup>th</sup> day of December..... 1982  
 ... David A. Traumbien... by Betty L. Shatto...  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 GPO-798-276  
 Umatilla County Surveyor  
 Date \_\_\_\_\_  
 Rec'd by \_\_\_\_\_  
 No. 82-136-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 23, 24, 25, and 26, monumented with the original unmarked basalt stone, 15 x 8 x 7 ins., firmly set 4 ins. in the ground, from which the original bearing trees:

A Pine, 30 ins. diam., bears N. 81° E., 136 lks. dist., with healed double blaze. (Record, N. 64° E., 134 lks.)

A Pine, 30 ins. diam., bears S. 57° E., 65 lks. dist., with scribe marks S25 visible on partially healed blaze. (Record, S. 38° E., 61 lks.)

A Pine, 35 ins. diam., bears N. 64° W., 195 lks. dist., with scribe marks E S2 visible on partially healed blaze. (Record, N. 42° W., 193 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 6 ins. in the ground, to solid rock, and supported in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S	R32E
S23	S24
S26	S25
1977	

No other suitable trees available within limits.

Deposit corner stone alongside iron post.

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-136-B