

USDA-FOREST SERVICE

Index

File No. R-21

T 3S R. 32E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. Sec 26 Cor. No. NE Cor

CORNER DIAGRAM

T3S R32E
S23 | S24
S26 | S25



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" l. pipe projecting 12" out of mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 29" P. Pine bears N80°E 89.5 ft. dist. tagged S81°W186 lk dist. (old BT) healed blaze.

A 35" P. Pine bears N64°W 129.4 ft. dist. tagged S64°E 195 lk (old BT) open blaze.

A 30" P. Stump bears S54°E 42.0 ft. dist. (old BT) visible scribing in wood near stump.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From Pearson Creek Road #54 to road #54-100 (Pole Mill Road) 400 ft. West then 100 ft. South to corner.

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-287

Filed At Umatilla Nat. Forest

Object Ident. Trees

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Willie R. Wells

Title

PLS 1106

Division

Headquarters

Date

September 23, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post, with 54-4 sign attached, on section line near corner.
Cap is standard BLM. Cap marked:

T3S R32E
S23 S24
S26 S25
1977

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 27" Red Fir bears S13° W 255.5 ft. dist. marked T3S R32E S26 BT.

A 9" P. Pine bears S48° E 115.0 ft. dist. marked T3S R32E S25 BT.

Painted the blaze faces and 6" bands around bearing trees red. Tagged bearing trees with 54-3 & 4 signs as needed, new BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 9/23/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by D. L. Kaufman PLS

Index File No.
R-21

T. 3S R. 32E

M. W.M.

Tract or Surv. No. S26

Cor. NE COR