


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

S-17

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 15" in ground with mound of stone to cap, from which:

A 11" dia. Grand Fir bears S71°E 38.0 ft. dist. marked: N 1/16 S 26 BT.


A 12" dia. Spruce bears S 15 1/2°W 22.5 ft. dist. marked: N 1/16 S27 BT.

A steel fence post, w/54-2 & 9 signs, 3 ft plus East of corner. Blaze faces and a 6" band around bearing trees were painted red. Trees were tagged w/54-3 & 9 signs. New BTS have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTS.

Set corner on October 14, 1982.

Cap marked:



Witnessed by: Leslie E. Wilson
Larry Henshaw

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor County of... Umatilla

State of... Oregon I hereby certify that the within instrument was filed in this office

for record on the 12 day of September, 1982

David H. Baumgardner *Betty L. Shatto*
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B
☆ GPO-798-276