


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-15

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" I. pipe 22" in ground and surrounded with mound of stone, from which:

A 14" P. Pine bears S17°E - 88.3 ft. dist. marked: T3S R32E C 1/4 S27 BT.

A 18" P. Pine bears S87°W - 32.3 ft. dist. marked: T3S R32E C 1/4 S27 BT.

Set steel fence post North and East of corner (near corner), w/54-2 & 9 signs attached.

Painted blaze faces and 6" band around bearing trees red. Tagged trees, with 54-3 & 9 signs. New BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush. Used steel tape and magnetic compass 19 3/4° East declination.

Corner set on October 14, 1982

Cap marked:

T3S R32E  
C 1/4 . S27  
1982  
PLS 1106

Witnessed by: Leslie E. Wilson  
Larry Henshaw

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of County Surveyor County of Umatilla

State of Oregon, I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

*David H. Hunsman* by *Betty Schatto*

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-136-B

☆ GPO-728,276