

USDA-FOREST SERVICE

Index

File No. T-15

T 3S R. 32E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. S 27

Cor. No. C 1/4

CORNER DIAGRAM

T3S R32E

C 1/4 . S27



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #54 to road #5412, then West to road #010, then North 3/4 miles then South 100 feet to corner.
In meadow west of old cabin.

Signature
William R. Wells

Title
PLS 1106

Division

Headquarters

Date
October 13, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 22" in the ground and surrounded with mound of stone. Set steel fence posts, w/54-9 sign and 54-2 signs, North and East near corner.

T3S R32E
C 1/4 . S27
Cap Marked: 1982
PLS 1106

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 14" P. Pine bears S17°E - 88.3 ft. dist. marked: T3S R32E C 1/4 S27 BT.
 A 18" P. Pine bears S87°W - 32.3 ft. dist. marked: T3S R32E C 1/4 S27 BT.
 Painted red 6" band around bearing trees and blaze faces. Tagged trees w/54-3 & 9 signs.
 New BTS have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W. R. Wells Title Surveyor Date 10/14/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: Leslie E. Wilson
 Larry Henshaw

Index File No. T-15 T. 3S R. 32E M. W.M. Tract or Surv. No. S27 Cor. C 1/4