


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-18

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2/12" brass cap on 2 1/2" x 30" I. pipe 12" in ground with mound of stone to cap from which:

A 17" dia. P. Pine bears East 66.0 ft. dist. marked: CW 1/16 S26 BT.

A 11" dia. W. Fir bears S23 1/2°E 133.1 ft. dist. marked: CW 1/16 S26 BT.

A steel fence post with 54-2 and 9 signs is set North of corner.


The blaze faces and 6" bands around the bearing trees were painted red. Trees were tagged with 54-3 and 9 signs. New BTs have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Set Corner monument on October 14, 1982.

Cap Marked:

Witnessed by: Leslie E. Wilson
Larry Henshaw



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Daniel H. Krumboltz by *Betty L. Shatto*

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B