


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-13

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner position a 4" x 4" x 4" post was set 2 ft. in ground on slight North slope from which:



- A 6" dia. Fir bears S70°W 9 lks dist. marked T3S R32E S33 BT.
- A 6" dia. Fir bears N38°W 58 lks dist. marked T3S R32E S28 BT.
- A 8" dia. Pine bears N28°E 37 lks dist. marked T3S R32E S27 BT.
- A 6" dia. Pine bears S68°E 14 lks dist. marked T3S R32E S34 BT.

Remonumentation done in 1977 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

3" brass on 2 1/2" I. pipe protruding 12" from ground from which:

- A 15" dia. W. Fir Snag bears S78°W 5.7 ft. dist. tagged N70°E 9 lk dist. (old BT) Partially healed blaze.
- A 18" dia. Tamarack bears N43°W 38.2 ft. dist. tagged S38°E 58 lk dist. (old BT) open blaze.
- A 18" dia. Red Fir bears S38 1/2°E 43.3 ft. dist. tagged N38°W 66 lk dist. - Recent blaze.
- A 13" dia. Red Fir bears S31°W 61.2 ft. dist. tagged N32°E 93 lk dist. - Recent blaze.
- A 16" dia. Red Fir bears N50°E 96.0 ft. dist. tagged S49 1/2° W 146 lk dist. - Recent blaze.


Description of monument and accessories established to perpetuate the original location of this corner:

- Set steel fence post, with 54-4 sign, on section line near corner.
- Painted 6" band around bearing trees and blaze faces red. Tagged trees with 54-3 & 4 signs where needed.
- Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

The corner was maintained on September 23, 1982

Cap is standard BLM cap marked:

Witnessed by: D. L. Kaufman PLS



REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of.....County Surveyor.....County of.....Umatilla
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the 15th day of December, 1982
 Daniel H. Trumbull by Betty J. Slatta
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd by _____
 No. 82-136-B

History Of 1977 BLM Remonumentation

The cor. of secs. 27, 28, 33, and 34, determined from the remains of the original bearing trees:

A Fir Snag, 12 ins. diam., bears S 80° W., 9 lks. dist., with fragmentary scribe marks visible on partially healed blaze. (Record, S. 70° W.)

A Fir, 17 ins. diam., bears N. 43° W., 58 lks. dist., with scribe marks R3 visible on partially healed blaze. (Record, N. 38° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, with brass cap marked:

T3S	R32E
S28	S27
S33	S34
1977	

from which new bearing trees

A Fir, 15 ins. diam., bears N. 49½° E., 146 lks. dist., mkd. T3S R32E S27 BT.

A Fir, 18 ins. diam., bears S. 38° E., 66 lks. dist., mkd. T3S R32E S34 BT.

A Fir, 12 ins. diam., bears S. 32° W., 93 lks. dist., mkd. T3S R32E S33 BT.

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd by _____

No. 82-136-B