


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V-17

History of original corner establishment: Corner was originally established by George S. Pershin, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a 14" x 12" x 4" basalt stone was set from which:



- A 10" Pine dia. bears S62°W 20 lks.
- A 12" Pine dia. bears N83°W 114 lks.
- A 10" Pine dia. bears S38°E 91 lks.
- A 10" Pine dia. bears N82°E 122 lks.

Remonumentation was done in 1977 by BLM.

Description of corner evidence found:

A 3" brass cap on 2 1/2" l. pipe set in mound of stone from which:

- A 32" P. Pine bears S72°W 13.0 ft. tagged N70°E 20 lk (original BT) open blaze.
- A 38" P. Pine bears N80°W 75.9 ft. tagged S 79° E 116 lk (original BT) healed blaze.
- A 26" P. Pine bears S49 1/2°E 60.3 ft. tagged N47 1/2°W 91 lk (original BT) partially healed blaze.
- A 40" P. Pine bears N86°E 81.9 ft. tagged S 86°W 122 lk (original BT) healed blaze.


Description of monument and accessories established to perpetuate the original location of this corner:

- Set steel fence post on section line and attached sign 54-4.
- Painted 6" band around bearing trees red and face of blaze. Tagged trees with 54-3 & 4 signs where needed.
- Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

This corner was maintained on September 22, 1982.

Cap is a standard 3" BLM cap marked:

Witnessed by: D. L. Kaufman PLS



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

David A. Krumbein by Betty Shatto (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date \_\_\_\_\_

Rec'd. by \_\_\_\_\_

I.C. 82-136-B

History of 1977 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 26, 27, 34, and 35, monumented with the original unmarked basalt stone, 14 x 12 x 4 ins., loosely set 1 in. in the ground, from which the original bearing trees:

A Pine, 40 ins. diam., bears N. 86° E., 122 lks. dist., with healed blaze. (Record, N. 82° E.)

A Pine, 27 ins. diam., bears S. 47½° E., 91 lks. dist., with fragmentary scribe marks visible on open blaze. (Record, S. 38° E.)

A Pine, 26 ins. diam., bears S. 70° W., 20 lks. dist., no marks visible on partially healed blaze. (Record, S. 62° W.)

A Pine, 36 ins. diam., bears N. 79° W., 116 lks. dist., with healed blaze. (Record, N. 83° W., 114 lks.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 20 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S	R32E
S27	S26
S34	S35
1977	

Deposit corner stone alongside iron post.

Corner is located 205 lks. south of gravelled road, 15 lks. wide, bears S. 80° E. and N. 80° W.

RECEIVED BY  
Umatilla County Surveyor  
Date \_\_\_\_\_  
Rec'd By \_\_\_\_\_  
No. 82-136-B