

CORNER RESTORATION FORM

Township 4N Range 28E Section 2,3,10,11 County UMATILLA

State OREGON Date 5-22-2019 Number E-17

Corner Designation: 2,3,10,11

Previous Renewals: ORIGINAL SOURCE OF CORNER

ORIGINALLY SURVEYED IN 1860 BY HAFT UNDER CONTRACT #93. HE SET POST IN

MOUND w/TRENCH, MADE PITS & DEPOSITED A PINT OF CHARCOAL.

Accessories Found: FOUND 1/2" IRON REBAR NO CAP; N42°37'W 72.10 FT.

ORIGIN UNKNOWN.

Condition Report Only


- Not Found
- Renewed
- Surveyed In
- Referenced

MONUMENT DETAIL

Found Set

BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE
COORDINATES NORTH ZONE:

NORTHING: 798163.43
EASTING: 8510376.72



BRASS CAP HAS NO STAMPINGS
CENTER PUNCH MARK ONLY

Monument & Accessories Set (Procedure and Description)

FOUND 2 1/2" BRASS CAP IN MONUMENT WELL 6" BELOW AC, AS PER COUNTY SURVEY 90-65-C; NOT FOUND 5/8 IRON PIN AS PER

COUNTY SURVEY 18-011-B.

CHISELED "X" IN STREET LIGHT BASE; N48°42'E 63.97 FT.

CHISELED "X" IN STREET LIGHT BASE; S52°18'E 81.55 FT.

SET MAG NAIL & 1-1/2" WASHER IN POWER POLE MARKED PLS 61420 ; S26°55'W 68.54 FT.

Sketch of Monument, Accessories and General Area

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Jane King

**OREGON
MAY 10, 2011
LANGE CLARK KING
61420**

RENEWALS: 6/30/2021

Agency: CK3, LLC
945 W. ORCHARD
HERMISTON OREGON 97838
OFFICE: 541-567-2345
FAX: 541-567-2305
WEB: CK3LLC.NET
Field Book # 0-325

**COUNTY SURVEYOR
RECORDING INFO**

Received _____

Filled _____

Survey No. _____

Drawing No. _____

Index No. E-17

19-080-C