

OREGON CORNER RESTORATION FORM

Section 10 Township 4N Range 28E

G-13

County UMATILLA Date 11/95

CORNER DESIGNATION

W 1/4

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals/Surveys, etc. ORIG. SURVEYED IN 1860 By HAFT  
In 1980 Krumbein Set a B.C. in place CONTRACT # 93  
of 7/8" Iron Rod

Monument(s) & Accessories Found: (Condition and Source)

End Krumbeins 1980 BC stamped 1981 in Mon. Box  
End 5/8" Rebar N 89° 30' 55" W 30.17 feet from the corner  
End nail @ 1/16 cor S 89° 41' 15" E 1320.22 feet from cor.

Monument Detail

Sketch



Monument Set (Procedures and Description)

AFTER KRUMBEIN'S B.C. was dug out by pipeline construction  
in its place I set 5/8" x 30" rebar with 2" Alum Cap  
stamped as above at surface of pavement

New Accessories

an alum tag #951 in P. Pole Bears N 49° 03' 15" E 40.83  
an alum tag #951 in P. Pole Bears N 86° 09' 55" W 24.43  
a large nail with alum tag #951 driven in top of 7" Locust stump Bears  
S 36° 11' 15" E 47.37

Location & Comments

At the intersection Compass Declination  
of Ridgeway & 11<sup>th</sup> St. Firm/Agency EDWARDS  
SURVEYING  
Address P.O. Box 763  
HERMISTON, OR 97038  
Party Chief D. Edwards  
Notes  
Witness J. Coppock

Surveyor's Seal

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
 JULY 16, 1971  
 G. DENNIS EDWARDS  
 951

RENEWS 12/31/95

09.39.A