

OREGON CORNER RESTORATION FORM

SECTION 7 TOWNSHIP 4 N RANGE 28 E J-3

COUNTY: UMATILLA DATE 12/95

CORNER DESIGNATION

S 1/4 COR

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed by Haft in 1860  
I found a 1 " iron bar in a 1978 survey for Jim Kooch  
I set BC incorrectly in 1994

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Fnd a round headed bolt S 88° 44' 21" E 2.92 feet from corner. Orig. unknown.  
Fnd a 1/2" rebar N 44° 26' 26" E 28.28 feet from cor. set by me in 1978 sur. for Kooch.  
Fnd. my 1994 2 3/8" BC S 50° 50' 31" E 1.04 feet from the cor.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

By retracing my 1978 Kooch survey I reset the 1"X30" Iron Pipe with a 2 3/8" Brass cap stamped as above at the paved surface.

NEW ACCESSORIES From which

An alum. tag #951 in a 20" locust bears N 40° 46' 21" W 33.18 feet

An Alum. tag #951 in a P. Pole bears N 27° 37' 26" E 45.44 ft  
A 1/2" rebar bears N 44° 26' 26" E 28.28 feet

A round headed bolt bears S 88° 44' 21" E 2.92 feet

An alum. tag # 951 in a P. Pole bears S 39° 36' E 36.24 feet

LOCATION & COMMENTS

At the intersection of Bridge Rd. & Lewis Rd.

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON  
OREGON, 97838

PARTY CHIEF D. EDWARDS  
NOTES  
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/95

RECEIVED BY

Umatilla County Surveyor

Date 1-96

Rec'd by KR

No. 96-14-R