

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4N RANGE 28 E

N-21

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

Northeast Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal. In 1973 Krumbein set a 2 1/2" Brass Cap on 1" Iron pipe in a survey in Section 14.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" Brass Cap on 1" pipe, stamped as below.

MONUMENT DETAIL

SKETCH

T4N R28E  
14 13  
23 24  
PLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Attached Witness Corner signs on North and South guard posts set around Corner. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 37° 20' 20" E 425.51 feet with Bearing Object sign attached.  
A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears N 89° 15' 12" W 18.00 feet in raised mound. Bearing Object and Witness signs attached to Cedar post.  
A 1" x 29" Galvanized pipe Bears S 0° 12' 53" W 3.00 feet with Alum. tag #951 attached.  
Center of manhole lid Bears N 83° 32' 10" E 559.46 feet.

LOCATION & COMMENTS

From intersection of U.S. Hwy #395 and Airport Road, go West on graveled road 0.1 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS  
NOTES  
WITNESS S. BENEFIT

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RECEIVED BY

Umatilla County Surveyor  
Date 4-92  
Rec'd By KE  
No. 92-45-C