

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

P-13

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

East 1/4 Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
 1/4
 21 22
 1991
 LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion, I set 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped as above, 1.0 ft. below surface of ground. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in power pole Bears N 13° 52' 20" W 133.43 feet with Bearing Object sign attached.
 A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, 0.1 ft. above ground in N-S fence line Bears N 90° 00' W 14.83 feet. Drove steel fence post with Bearing Object and Witness signs attached.
 An Alum. tag #951 in power pole Bears S 07° 12' 40" W 271.85 feet with Bearing Object sign attached.
 Center of Pivot #321 Bears N 79° 11' 20" E 1346.80 feet.

LOCATION & COMMENTS

From intersection of Buttercreek Hwy. and Feedville Rd. go East on Feedville Rd. 0.45 mile, then go North on feedlot road 0.5 mile to Corner.

COMPASS DEC.
 FIRM EDWARDS SURVEYING
 P.O. BOX 763, HERMISTON,
 OREGON, 97838
 PARTY CHIEF D. EDWARDS
 NOTES
 WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1871
 G. DENNIS EDWARDS
 951

RECEIVED BY

Umatilla County Surveyor
 Date 4-92
 Rec'd By KR
 No. 92-45-C