

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4N RANGE 28 E

P-17

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

West 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 5/8" rebar in centerline of paved road. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E  
1/4  
22 23  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I set a 2 3/8" Brass Cap, stamped as above, on a 1" x 10" Iron pipe over 5/8" rebar. Brass Cap is 0.3 ft. below surface, inside of 5" P.V.C. pipe and an Alum. County Monument Box set in concrete flush with asphalt. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951 Bears N 89° 24' W 32 feet, with Witness sign attached to RR tie.  
An Alum. tag #951 on Power pole Bears S 30° 49' W 60.05 feet with Bearing Object sign attached.  
An Alum. tag #951 on Power pole Bears S 52° 32' 40" E 84.51 feet with Bearing Object sign attached.  
A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears S 89° 24' 00" E 32 feet. Witness sign attached to RR tie.

LOCATION & COMMENTS

From intersection of Feedville Road and Hinkle Road, go North 1/2 mile on Hinkle Road to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

NOTES  
WITNESS S. BENEFIT

*G. Dennis Edwards*

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-c

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951