

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

R-13

COUNTY: UMATILLA DATE 1/92

CORNER DESIGNATION

Southeast Corner

CONDITION REPORT ONLY  
NOT FOUND  
RENEWED  
UNRECORDED  
x SURVEYED IN  
x REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal. In 1958, Ralph Thompson set 2" Iron pipe at location of an "old rusted I.P."

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2" Iron pipe 3" below the surface of paved road.

MONUMENT DETAIL

SKETCH

T4N R28E  
21 22  
  
28 27  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I drove 1/2" rebar inside pipe and set a 2 3/8" Brass Cap on 1" x 3/4" long Iron pipe over it, stamped as above, 0.2 below surface of paved road in 5" P.V.C. and in an Alum. Umatilla County Monument Box, set in concrete, flush with surface. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 2 2/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 0° 12' 35" E 23.60 feet.  
An Alum. tag #951 in RR tie fence post Bears N 25° 06' W 27.60 feet with Bearing Object sign attached. An Alum. tag #951 in Power pole Bears S 42° 16' 30" W 45.55 feet with Bearing Object and Witness sign attached. An alum. tag #951 in Power pole Bears S 22° 21' 00" E 37.09 feet with Bearing Object sign attached.

LOCATION & COMMENTS

From intersection of Buttercreek Hwy. and Feedville Road, go East on Feedville Rd. 0.45 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS  
NOTES  
WITNESS S. BENEFIT

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KR

No. 92-45-C