

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4N RANGE 28 E

R-19

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
23
1/4
26
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion, I set a 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped as above, flush with pavement and poured concrete around it. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 0° 01' E 33.00 feet. Drove steel fence post and attached Bearing Object and Witness signs.

An Alum. tag #951 in power pole Bears S 85° 37' 00" W 328.68 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951, Bears S 0° 01' W 33.00 feet. Drove steel fence post and attached Bearing Object and Witness signs.

An Alum. tag #951 in power pole Bears S 10° 21' 50" E 29.37 feet with Bearing Object sign attached.

LOCATION & COMMENTS

From intersection of Hinkle Rd. and Feedville Road, go East on Feedville 0.5 mile to Corner.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 18, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 4-92
Rec'd By KK
No. 92-455