

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

R-9

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

Southwest Corner

CONDITION REPORT ONLY

NOT FOUND

RENEWED

UNRECORDED

x SURVEYED IN

x REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

Walt Cramer set a 1 1/2" I. pipe in a June 1979 survey for Griffitts in Section 20

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found a 1 1/2" x 36" Iron pipe set by Cramer in June 1979 survey for Griffitts.

MONUMENT DETAIL

SKETCH

T4N R28E
20 21

29 28
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

In place of 1 1/2" Iron pipe, I set a 2 3/8" Brass Cap, stamped as above, on a 1" x 30" Iron pipe with found pipe (sawed in half) placed beside Brass Cap. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 2 1/4 O.D. x 26" Galvanized Iron pipe Bears N 57° 21' 10" E 63.37 feet. A 1/2" Grd. rod Bears N 22° 25' 10" W 48.12 feet with Bearing Object sign attached to power pole. An Alum. tag #951 in Power pole Bears S 75° 18' 10" W 19.48 feet with Bearing Object sign attached. A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears South 15.33 feet. Drove steel fence post with Witness and Bearing Object signs attached.

LOCATION & COMMENTS

Corner is at the intersection of Feedville and Keller Roads.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C