

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-11
DIAGRAM

History of original corner establishment:
Dave Krumbein, PLS 933, and Wayne Harris, PLS 346,
found a stone in 1975, but did not monument the
point.

T4N R28E

C1/4+S28

1987
PLS 699

Description of corner evidence found:

I did not find any stone or record of one being set, therefore, the corner
is being set by this survey.

Description of monument and accessories I established to perpetuate the
original location of this corner:

Set a 2"x30" galvanized pipe with a 2 1/2" brass cap, marked as shown in the
diagram, 22" in the ground to hardpan, about 0.8' W of highway R/W fence
at a point as determined by the procedures set forth in the MANUAL OF
INSTRUCTIONS FOR THE SURVEY OF PUBLIC LANDS for the subdivision of
sections. Built a mound of rock and concrete pieces to be 24" in diameter
by 8" high around the monument.

Telephone pole bears N4° 12'E, 90.80'
Corner Pole of a 69KV power line bears N63° 27'E, 117.5'

I, Leland L. Myers, P.O. Box 98, Sumpter, OR 97877,
do hereby certify that on December 24, 1987, I
established the corner as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 9, 1955
LELAND LEE MYERS
699

FILED

IN THE OFFICE OF THE Umatilla COUNTY SURVEYOR

THIS 20 DAY OF February, 1988

David H. Kilmer
Umatilla County Surveyor

RECEIVED BY

Umatilla County Surveyor

Date 2-20-88

Rec'd By AT

No. 88-15-C

T4N R28E T-11