

OREGON CORNER RESTORATION FORM

SECTION 28 TOWNSHIP 4N RANGE 28 E

T-13

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

East 1/4 Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 1/2" rebar. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E

1/4
28 27

1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I set a 2 3/8" Brass Cap, stamped as above, on 1" x 30" Iron pipe with 1/2" rebar buried inside. Witness sign on steel fence post set in E-W fence. See my County Survey #1991-2.

NEW ACCESSORIES From which

- An Alum. tag #951 in Power pole Bears S 29° 55' 10" W 59.02 feet with Bearing Object sign attached.
- A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951 Bears South 209.98 feet, set 0.4 ft. above surface, dug 4 ft. diameter trench around raised mound. Witness and Bearing Object signs on steel fence post.
- An Alum. tag #951 in Power pole Bears S 74° 33' E 241.38 ft. with Bearing Object sign attached.
- An alum. tag #951 in a 10" fence post Bears S 83° 51' 10" E 4.43 feet with Bearing Object sign attached.

LOCATION & COMMENTS

Corner lies in an E-W fence line 0.4 mile East and 0.5 mile South of intersection of Buttercreek Hwy. and Feedville Road.

SURVEYOR'S SEAL

COMPASS DEC.
 FIRM EDWARDS SURVEYING
 P.O. BOX 763, HERMISTON,
 OREGON, 97838
 PARTY CHIEF D. EDWARDS
 NOTES
 WITNESS S. BENEFIT

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RECEIVED BY
 Umatilla County Surveyor
 Date 4-92
 Rec'd By KK
 No. 92-45-C