

OREGON CORNER RESTORATION FORM

SECTION 28 TOWNSHIP 4N RANGE 28 E

T-9

COUNTY: UMATILLA DATE 1/92

CORNER DESIGNATION

West 1/4 Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal. In 1987, Leland Myers set a 2 1/2" Brass Cap on a 2" Iron pipe from Railroad ties.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" Brass Cap on 2" Iron pipe N 7° 26' 42" W 11.59 feet from the corner.

MONUMENT DETAIL

SKETCH

T4N R28E
 1/4
 29 28
 1991
 LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion, I set a 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped as above, 0.6 feet above ground in 3 foot raised rock and dirt mound. Drove steel fence post with Bearing Object and Witness signs attached. See my 1991-2 County remonumentation survey.

NEW ACCESSORIES From which

- 2" Alum. cap on 5/8" rebar stamped, RM 74.9 1987 PLS 699, Bears N 82° 07' 00" E 74.09 feet.
- A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 0° 24' 51" E 30.00 feet. Drove steel fence post and attached Bearing Object and Witness signs.
- 2" Alum. cap on 5/8" rebar stamped, RM 32.1 1987 PLS 699, Bears N 01° 47' 40" W 43.62 feet.
- A 2 3/8" Brass Cap on 1" x 30" Iron pipe, stamped W.C. LS 951, Bears S 0° 24' 51" W 354.75 feet.

LOCATION & COMMENTS

From Butter Creek Hwy. just South of U.P.R.R. overpass, go West along a gravel road 0.5 mile. Corner lies just North of a R.R. spur.

COMPASS DEC.
FIRM EDWARDS SURVEYING
 P.O.BOX 763, HERMISTON,
 OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES
WITNESS S. BENEFIT

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C

SURVEYOR'S SEAL

**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

G. Dennis Edwards

OREGON
 JULY 16, 1971
G. DENNIS EDWARDS
 951