

OREGON CORNER RESTORATION FORM

SECTION 26 TOWNSHIP 4N RANGE 28

V-19

COUNTY: UMATILLA DATE 11/91

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed under Contract #93 in October 1860 by Taft. He set post.

MONUMENTS & ACCESSORIES FOUND: Condition and Source
Nothing found.

MONUMENT DETAIL

SKETCH

T4N R28E
26
1/4 . 35
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set 2 3/8" Brass Cap, stamped as above, on 1" x 30" Iron pipe flush with ground, drove steel fence post with Witness sign attached, 2 feet East. See my County Survey #1991-2.

NEW ACCESSORIES From which

An Alum. tag #951 in 7" Monkey tree Bears N 11° 34' W 31.70 feet, with Bearing Object sign attached.
A 1 3/8" x 30" Iron pipe Bears N 89° 23' W 12.28 feet, stamped 951 on East side.
A 1 1/4" x 36" rebar Bears South 7.97 feet, stamped 951 on top.
Center of 6" Test well casing Bears S 84° 27' 25" E 214.00 feet.

LOCATION & COMMENTS

From the Guard shack at "SIMPLIT POTATO PLANT" entrance, go East along RR tracks 1.5 miles. Corner lies on South edge of a road to the South of a gravel pit.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES

WITNESS S. BENEFIT

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-C

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951