

OREGON CORNER RESTORATION FORM

Section 5 Township 4N Range 29E

A-7

County Umatilla Date 3/95

CORNER DESIGNATION

N 1/4

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. NONE

Monument(s) & Accessories Found: (Condition and Source)

NONE

Monument Detail

Sketch



Monument Set (Procedures and Description)

By single proportion set 5/8" x 30" rebar stamped as
above, a 2" Alum. Cap FLUSH with Pavement
See my 1992 Area 1 public Monumenting survey

New Accessories

From which
5/8" Rebar with Plastic Cap # 2431
The SW Cor. Parcel 2, P. Plat 1993-22 Bears N 70° 38' 04" W 168.81 ft.
5/8" Rebar with Plastic Cap # 2431
The SE Cor. Parcel 2, P. Plat 1993-22 Bears N 76° 01' E 134.78 ft.
An Alum Tag stamped 951 in P. Pole Bears S 31° 11' 40" E 23.32 ft
A 2 3/8" B.C. on 1" x 30" I. Pipe Stamped W.C. Bears S 0° 06' 56" W 18.93 ft

Location & Comments

From intersection of Compass Declination _____
Cabana Rd & Punkin Firm/Agency Edwards
Center Rd. Go West Surveying _____
on Punkin Center Address P.O. Box 763
450 ft. to corner Hermiston, OR 97838
 Party Chief D. Edwards
 Notes _____
 Witness J. Coppock

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/95

RECEIVED BY

Umatilla County Surveyor

Date 4-95

Rec'd by KK

No. 95-59-B