

# OREGON CORNER RESTORATION FORM

SECTION 24      TOWNSHIP 4 NORTH    RANGE 29 EAST      N-23

COUNTY : UMATILLA      DATE 8-98

CORNER DESIGNATION

NORTH 1/4

— CONDITION REPORT ONLY  
— NOT FOUND  
— RENEWED  
— UNCOVERED  
 SURVEYED IN  
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

SKETCH

MONUMENT DETAIL



MONUMENT SET ( PROCEDURES AND DESCRIPTION )

BY SINGLE PROPORTION, I SET 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE, 3" ABOVE THE SURFACE.

NEW ACCESSORIES FROM WHICH

A 5/8" X 24" IRON REBAR WITH PLASTIC CAP #951 LIES N 89°.59'46" E, 170.02 FEET.  
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES N 89°.59'00" E, 18.98 FEET.  
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES S 89°.59'00" W, 23.00 FEET.  
A 3/4" IRON BOLT IN THE NORTH WEST CORNER OF AN 11' X 11' CONCRETE PAD LIES S17°.15'20" E, 140.65 FEET.

LOCATION AND COMMENTS

COMPASS DEC.

SURVEYOR'S SEAL

FIRM/AGENCY  
EDWARDS SURVEYING  
P.O. BOX 763  
HERMISTON, OREGON 97838  
97838

PARTY CHIEF  
D. EDWARDS

NOTES

WITNESS  
RICK SMITH

**RECEIVED BY**  
Umatilla County Surveyors  
Date 10-98  
Rec'd By SK  
No. 98-213-C

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/99