

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4 NORTH RANGE 29 EAST R-21
COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

SE CORNER

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY DOUBLE PROPORTION I SET A 5/8" X 30" IRON REBAR WITH A 2" ALUMINUM CAP STAMPED AS ABOVE FLUSH WITH THE SURFACE OF A PAVED ROAD, 5.7' NORTH OF CENTER LINE.

NEW ACCESSORIES FROM WHICH

A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES N 77°.56'37" W, 71.39 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES S 57°.41'40" W, 58.66 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES S 2°.01'00" W, 48.93 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES N 9°.17'30" W, 20.96 FEET.

LOCATION AND COMMENTS

FROM THE INTERSECTION OF LOOP ROAD WITH FEEDVILLE ROAD, GO EAST ON FEEDVILLE ROAD 1/2 MILE.

COMPASS DEC.

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/99

RECEIVED BY

Umatilla County Surveyor

Date 10-98

Rec'd By KK

No. 98-213-C