

OREGON CORNER RESTORATION FORM

SECTION 27 TOWNSHIP 4 NORTH RANGE 29 EAST T-17

COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

EAST 1/4

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE..

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND A 2" O.D. IRON PIPE 20" BELOW THE SURFACE OF A GRAVELED ROAD AT THE INTERSECTION OF TWO ROADS. NO RECORDED.

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

I DROVE A 5/8" X 24" IRON REBAR INSIDE THE IRON PIPE AND ATTACHED A 2" ALUMINUM CAP STAMPED AS ABOVE, 3" BELOW THE SURFACE.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG #951 ON A POWER POLE LIES N 29°.22'30" E, 34.33 FEET
AN ALUMINUM TAG #951 ON RXR TIE GATE POST LIES N 87°.41'00" E, 18.70 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES S 39°.59'00" W, 25.83 FEET.
AN ALUMINUM TAG #951 ON A TELEPHONE POLE LIES S 39°.57'00" E, 28.31 FEET.

LOCATION AND COMMENTS

COMPASS DEC.

SURVEYOR'S SEAL

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
CURTIS J. FAVOREL

RECEIVED BY
Umatilla County Surveyor
Date 10-98
Rec'd By KK
No. 98-213-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/99