

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 4N29V1 GEODETIC COORDINATE: NAD 83(91)

SECTION: SW COR S30 LAT: 45°47'28.84854" N
T. 4N., R. 29 E., W. M. LONG: 119°14'54.75832" W
UMATILLA COUNTY
OREGON

STATE PLANE CO-ORDINATES,
NAD 83-91, INT. FT. :

DATE SURVEYED: March, 1998

N: 777090.620

E: 8521316.445

SURVEYOR: DAVID L. HADDOCK
PLS 852

THETA: 0°53'15.05"

SCALE FACTOR: 0.99995465

ELEV: 624

FIRM: HADDOCK SURVEYING
P. O. BOX 1574
PENDLETON, OR 97801
(541) 276-2174

ELEV. DATUM: NGVD29

HORIZONTAL SECOND ORDER,
ORDER: CLASS I

LOCATION: From the Coe Street rail road crossing in the City of Stanfield go southwest on Seymour Street to Hoosier road. Go northwest on Hoosier road approximately 1/2 mile until the road turns to the west. continue to go northwest through the gate onto the private road along the south side of the railroad tracks. Follow this road approximately 3/4 of a mile. The cap is just outside the fence at the intersection of the private road and a north south fence on the south side of the road

STATION: Station is a 2 1/4 inch brass disc on a galvanized iron pipe. The cap is approximately 2 inches above the surface of the ground.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David L. Haddock

OREGON
JULY 12, 1966
DAVID L. HADDOCK
852

98-155-C